

Work Instruction		WO No.:	
		Date:	
<b>Scope:</b>			
<b>Team Leader:</b>		<b>Type:</b>	
<b>Activity:</b> Pedestrian Swing Gate Mechanism Like for Like Renewal			
<b>Reference:</b> PR S 40002, PR S 40008, PR S 40009, PR S 40010, PR S 40011			
Activity No.	Task No.	Work Description	Completed Name/Sign
<b>APPARATUS INSPECTION &amp; PREPARATION</b>			
1	1A	Ensure the new Pedestrian Swing Gate mechanism is of correct configuration. Inspect the equipment type and the configuration are in accordance with the specific design and compare to the existing Pedestrian Swing Gate mechanism	
	1B	Bell test and wire/null count the internal wiring of the new Pedestrian Swing Gate mechanism and compare to the specific circuit design and existing Pedestrian Swing Gate mechanism. Include a correlation of connected links and bridges to the circuit book. Visually inspect and insulation test the internal wiring of the new Pedestrian Swing gate mechanism. Ensure that circuit controller contacts are in the correct position as per the specific circuit design	
2	2A	On the existing Pedestrian Swing Gate mechanism, wire/null count the incoming terminals, including bridges, links and identify cable numbers on the terminals and compare to specific circuit diagram	
	2B	Document the disconnections on attached circuit diagram	
	2C	Conduct an apparatus inspection of the condition of the existing drive point fixings	
<b>SAFeworking &amp; DISCONNECTION FROM INTERLOCKING</b>			
3	3A	Switch the Cerberus monitor to "maintenance mode" to prevent any unnecessary alarms. Advise ICON Infrastructure of the intended work	
	3B	Ensure the level crossing and affected signalling equipment is booked out of use in accordance with PR S 40008. If temporary bridging is required, obtain authorisation for temporary bridging in accordance with PR S 40002	
	3C	Disconnect the level crossing and affected signalling equipment in accordance with PR S 40009. <b>Note:</b> The Pedestrian Swing Gate shall not to be tied open	
	3D	If applicable, apply temporary bridging in accordance with the authorisation. Test bridging in accordance with PR S 40002 to ensure the bridges are effective and that any contacts remaining in the circuit are functional	
<b>DISCONNECTION, REMOVAL AND INSTALLATION</b>			
4	4A	Open links in location for the Pedestrian Swing Gate mechanism tail cable/s	
	4B	Disconnect cable/s in the Pedestrian Swing Gate mechanism, protect ends and withdraw clear	
	4C	Disconnect the Pedestrian Swing Gate linkage arm and mounting bolts and remove the mechanism	
5	5A	Install the new Pedestrian Swing Gate mechanism, connect linkage arm and connect all securing nuts, bolts and split pins	
6	6A	Connect all cables in accordance with previously correlated circuit diagram.	
	6B	Inspect the cable/s for any signs of damage. Conduct an insulation test of the tail cable/s and record on circuit diagrams	
7	7A	Lubricate the Pedestrian Swing Gate hinges to ensure reliable operation	
<b>ADJUSTMENT</b>			
8	8A	Conduct a safety, security and reliability inspection of the fixings, locking tabs, parallel locking bush set screws, linkage arms, nuts, bolts and split pins. Ensure linkages are clear of adjacent fencing	

OFFICIAL

Activity No.	Task No.	Work Description	Completed Name/Sign
		<b>CERTIFICATION</b>	
	8B	Make any adjustments necessary to the Pedestrian Swing Gate mechanism drive, return spring, linkage arms and motor cut out to enable gate to become operational	
9	9A	Close all associated terminal links in the location and if applicable, remove any temporary bridging. <b>Note:</b> The testing that ensures temporary bridges are removed are done in steps 10 and 12, as part of the overall wire/null count and correspondence testing	
10	10A	Conduct a wire/null count on all terminals with incoming tail cable/s installation to circuit diagram. (NB: links to be counted as wire). Record on circuit diagram	
11	11A	Conduct a power test of the Pedestrian Swing Gate mechanism operation with the return spring disconnected; check the gate will open and close correctly from the fully open and closed positions. Adjust if required. Reinstall the return spring. Ensure the Pedestrian Swing Gate operates correctly with smooth, noise-free motion from the motor/gearbox. Ensure there is no hesitation of the gate movement to close when activated. Ensure motor power has reduced when the gate is in either the fully opened or closed position	
	11B	Test the indexed coupling by forcing the Pedestrian Swing Gate toward the closed position (from the fully open position) until the coupling produces a clicking noise. Release the swing gate and ensure it returns to the pre-set position	
	11C	Test the operation of the Pedestrian Swing Gate mechanism return spring, by ensuring the swing gate fully closes after the removal of power from the motor. Repeat test from 10 degrees of the fully closed position	
	11D	Ensure the Pedestrian Swing Gate when fully closed, cannot be forced open easily.	
12	12A	Conduct a correspondence test of the Pedestrian Swing Gate Normal detection (XNR) where applicable. Operate all gates to the closed position and open each gate in turn to ensure the XNR relay de-energises and restores. Observe the relevant contact to ensure it is of the correct type (N/O or N/C) and opens and closes correctly. <b>Note:</b> The above test incorporates the out of correspondence test for each corresponding pedestrian swing gate (Sydney-side and Country-side)	
	12B	Conduct a correspondence test of the Pedestrian Swing Gate Reverse detection (XRR) where applicable. Operate all gates to the open position and close each gate in turn to ensure the XRR relay de-energises and restores. Observe the relevant contact to ensure it is of the correct type (N/O or N/C) and opens and closes correctly <b>Note:</b> The above test incorporates the out of correspondence test for each corresponding pedestrian swing gate (Sydney-side and Country-side)	
13	13A	Ensure the tone generator DIP switch settings are correctly set. Ensure correct operation of the tone generator. Observe the relevant contact to ensure it is of the correct type (N/O or N/C) and opens and closes correctly	
	13B	Ensure correct operation of red-man light indication. Observe the relevant contact to ensure it is of the correct type (N/O or N/C) and opens and closes correctly	
14	14A	Ensure that any alarms raised with Cerberus monitor are cleared. Switch Cerberus monitor out of "maintenance mode"	
15	15A	Arrange with the signaller to conduct an operational test of the affected signalling equipment in association with the level crossing protection equipment. Ensure the Pedestrian Swing Gate mechanism is secure	
	15B	Book the level crossing and affected signalling equipment back into use.	

OFFICIAL

I certify that \_\_\_\_\_ Side Pedestrian Swing Gate mechanism  
the \_\_\_\_\_ at \_\_\_\_\_  
Level Crossing location has been correctly reinstated, inspected, tested and is fit for service.

\_\_\_\_\_  
Print Name

\_\_\_\_\_  
Position

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date