


# **Appendix D Noise and vibration impact assessment**

# Mascot Substation

Noise and Vibration Impact Assessment



## Mascot Substation

### Noise and Vibration Impact Assessment

Client: Transport for New South Wales

ABN: 18 804 239 602

#### Prepared by

**AECOM Australia Pty Ltd**

Level 21, 420 George Street, Sydney NSW 2000, PO Box Q410, QVB Post Office NSW 1230, Australia  
T +61 2 8934 0000 F +61 2 8934 0001 www.aecom.com  
ABN 20 093 846 925

02-Dec-2019

Job No.: 60600277

AECOM in Australia and New Zealand is certified to ISO9001, ISO14001 AS/NZS4801 and OHSAS18001.

© AECOM Australia Pty Ltd (AECOM). All rights reserved.

AECOM has prepared this document for the sole use of the Client and for a specific purpose, each as expressly stated in the document. No other party should rely on this document without the prior written consent of AECOM. AECOM undertakes no duty, nor accepts any responsibility, to any third party who may rely upon or use this document. This document has been prepared based on the Client's description of its requirements and AECOM's experience, having regard to assumptions that AECOM can reasonably be expected to make in accordance with sound professional principles. AECOM may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified. Subject to the above conditions, this document may be transmitted, reproduced or disseminated only in its entirety.

## Table of Contents

Executive Summary		i
1.0	Introduction	1
	1.1 Overview	1
	1.2 Background	1
	1.3 The Proposal	1
	1.4 Relevant guidelines	1
2.0	Existing noise environment	3
	2.1 Proposal area description	3
	2.2 Receivers	3
	2.3 Noise monitoring	6
	2.3.1 Instrumentation	6
	2.3.2 Unattended background noise monitoring results	6
	2.3.3 Attended noise monitoring	7
3.0	Assessment criteria	8
	3.1 Construction noise criteria	8
	3.1.1 Construction hours	10
	3.1.2 Construction noise management levels	10
	3.1.3 Sleep disturbance	11
	3.1.4 Construction road traffic noise	12
	3.2 Construction vibration criteria	12
	3.2.1 Structural damage	12
	3.2.2 Human comfort	13
	3.3 Operational noise criteria	14
	3.3.1 Intrusiveness noise levels	14
	3.3.2 Protecting noise amenity	14
	3.3.3 Tonality	16
	3.3.4 Maximum noise level assessment	17
4.0	Construction noise assessment	18
	4.1 Construction stages and scheduling	18
	4.2 Plant and equipment levels	18
	4.3 Noise modelling methodology	20
	4.3.1 Construction modelling assumptions	20
	4.4 Predicted construction noise impacts	20
	4.5 Sleep disturbance assessment	21
	4.6 Construction traffic assessment	22
5.0	Construction vibration assessment	23
6.0	Operational noise assessment	24
	6.1 Assessment overview	24
	6.2 Noise modelling methodology	24
	6.2.1 Meteorological conditions	24
	6.3 Noise sources modelled	24
	6.3.1 Maximum Noise levels	25
	6.4 Noise modelling results	25
	6.4.1 $L_{Aeq}$ noise levels	25
7.0	Mitigation measures	27
	7.1 Construction noise and vibration mitigation	27
	7.1.1 Construction Noise and Vibration Management Plan	27
	7.1.2 Community consultation and complaints handling	30
	7.1.3 TfNSW's CNVS - Additional mitigation measures	30
8.0	Conclusion	35
	8.1 Construction noise	35
	8.1.1 Construction traffic	35
	8.2 Construction vibration	35
	8.3 Operational noise	35

Appendix A	A
Acoustic terminology	
Appendix B	B
Logging results	
Appendix C	C
Construction noise contours	
Appendix D	D
Operational noise contours	

## Executive Summary

Transport for NSW (TfNSW) proposes to deliver service improvements on the T4 Illawarra Line, South Coast Line and T8 Airport Lines. The improvements would deliver greater capacity, reliability and connectivity for customers. To achieve this, TfNSW has developed the More Trains, More Services Program (the 'Program').

As part of the Program, it is proposed to construct a new traction substation at 166 O'Riordan Street, Mascot (the Proposal).

This noise and vibration impact assessment forms part of the Review of Environmental Factors (REF) which assesses the potential impacts of the Proposal on the environment. Relevant guidelines and assessment procedures have been followed to ensure all applicable regulatory requirements have been considered.

A survey has been undertaken of the existing conditions throughout the Proposal area. Buildings throughout the Proposal area have been reviewed to identify their likely use and the number of storeys. Background noise levels have been monitored at nearby a residential receiver location to identify the existing noise environment throughout the Proposal area. Appropriate noise criteria have been developed based upon this existing noise environment.

A construction noise impact assessment has been conducted in accordance with the *Interim Construction Noise Guideline* (ICNG) (DECC, 2009) and *Construction Noise and Vibration Strategy* (CNVS) (TfNSW, 2019). Reasonable worst-case construction scenarios have been assessed. Construction of the Proposal would occur both during standard construction hours and out-of-hours to minimise disruptions. The out-of-hours work would be subject to the processes outlined in Section 3.1.

The assessment of noise associated with the construction of the Proposal indicates some exceedances of the ICNG noise management levels at the most affected sensitive receivers. Exceedances of the noise management levels occur during the day and night at the most affected sensitive receivers during certain activities. The magnitude of these impacts is consistent with similar construction projects and highlights the need for effective noise mitigation and management planning.

Measures have been recommended to mitigate the construction noise impacts at adjacent sensitive receivers. Specific noise management and mitigation measures would be detailed in the contractor's Construction Noise and Vibration Management Plan. The recommended management and mitigation measures which would be considered in the plan include:

- Effective communication with community and affected receivers about mitigation measures
- Training of construction site workers
- Use of noise barriers
- Noise monitoring
- Appropriate selection and maintenance of equipment
- Scheduling of work for less sensitive time periods
- Situating plant in less noise sensitive locations
- Construction traffic management
- Respite periods.

Minimum working distances for vibration intensive construction works have been presented. Equipment size would be selected by the contractor taking into account the minimum working distances and the distance between the construction works and the most affected sensitive receiver. If works need to be undertaken within minimum working distances, vibration monitoring would be undertaken.

An operational noise assessment was undertaken in accordance with the *Noise Policy for Industry* (NPfI) (EPA, 2017). The results of this assessment found that the predicted noise levels due to operation of the new substation at Mascot were below the noise trigger levels determined in

accordance with the NPfI. It is recommended that the noise emissions of the facility be reviewed once the final equipment selections have been made. Based on the equipment noise level assumptions used in this report, no further mitigation is proposed.

## 1.0 Introduction

### 1.1 Overview

Transport for NSW (TfNSW) proposes to deliver service improvements in the T4 Illawarra Line, South Coast Line and T8 Airport Lines, including capacity, reliability and connectivity improvements for customers. To achieve this, TfNSW has developed the More Trains More Services Program (the Program).

As part of the Program, it is proposed to construct a new traction substation building at 166 O’Riordan Street, Mascot (the Proposal).

AECOM Australia Pty Ltd (AECOM) has been commissioned by TfNSW to carry out a noise and vibration impact assessment for the construction and operation of the Proposal.

A glossary of acoustic terminology is provided in Appendix A.

### 1.2 Background

The Proposal would contribute to the transformation of the rail network to provide customers with more reliable, high capacity turn up and go services. In recent years, infrastructure constraints have been a barrier to enhancing services. In response to growth in demand on these lines, the next stages of the program will deliver a 30 per cent uplift in the total number of peak services on T4 Eastern Suburbs and Illawarra Line, the South Coast Line and the T8 Airport and South Line.

### 1.3 The Proposal

The Proposal would include a new traction substation at 166 O’Riordan Street, Mascot.

The two-level substation would accommodate the following equipment and facilities:

- loading dock on first floor
- a switchroom including HV and 1500 V DC switchgear
- rectifiers
- transformers
- reactors
- office space and staff amenities (including kitchenette and emergency showers)
- batteries
- telecommunications and control systems equipment
- parking for two light vehicles.

### 1.4 Relevant guidelines

The relevant policies and guidelines for noise and vibration assessments in NSW that have been considered during the preparation of this report include:

- *Interim Construction Noise Guideline (ICNG)*, Department of Environment and Climate Change, 2009
- *Construction Noise and Vibration Strategy (CNVS)*, Transport for New South Wales (TfNSW), 2019
- *Assessing Vibration: A Technical Guideline (AVATG)*, Department of Environment and Conservation (DEC), 2006



- DIN 4150: Part 2-1999 *Structural vibration – Human exposure to vibration in buildings* (Deutsches Institut für Normung 1999)
- DIN 4150: Part 3-2015 *Structural vibration – Effects of vibration on structures* (Deutsches Institut für Normung 2015)
- AS2436-2010 Guide to noise and vibration control on construction, demolition and maintenance sites
- BS5228:2009 Part 1 2009 Code of practice for noise and vibration control on construction and open sites
- ISO 9613-2:1996 Acoustics - Attenuation of sound during propagation outdoors - Part 2: General method of calculation
- AS60076.10.1:2009 Power transformers Determination of sound levels - Application guide
- *NSW Road Noise Policy (RNP)*, Department of Environment, Climate Change and Water (DECCW), 2011
- *Noise Policy for Industry (NPfI)*, Environment Protection Authority (EPA), 2017

## 2.0 Existing noise environment

### 2.1 Proposal area description

The Proposal is located at 166 O’Riordan Street, Mascot, NSW. The site is approximately 7 kilometres south of the Sydney CBD. The Proposal would be undertaken wholly within the suburb of Mascot in the Bayside Local Government Area (LGA).

The two-level substation would accommodate the following equipment and facilities:

- loading dock on first floor
- a switchroom including HV and 1500 V DC switchgear
- rectifiers
- transformers
- reactors
- office space and staff amenities (including kitchenette and emergency showers)
- batteries
- telecommunications and control systems equipment, and
- parking for two light vehicles.

The Mascot Substation (MS) is bounded by O’Riordan Street to the west. Premises to the north, south, east and west are located within land zoned B5 Business development and comprise commercial and industrial uses. Residences are located approximately 100 metres to the south and further to the east.

The acoustic environment is considered to be typically urban, comprising mainly road and air traffic noise.

An overview of the Proposal area showing the noise monitoring location and assessment receivers is shown in Figure 1 below.

### 2.2 Receivers

Residential and non-residential receivers potentially affected by the construction and operation of the Proposal have been identified within the Proposal area and are presented in Figure 1. Receivers comprise high density multi-storey residential and low density residential properties located within the suburb of Mascot. These noise sensitive receivers were identified using aerial photography, and their occupational uses reviewed. Assessment criteria have been determined for all receivers as outlined in Section 3.0.

To provide a comprehensive assessment of the operation of the Proposal, seven representative residential receivers, four commercial receivers and two hotel receivers surrounding the Proposal, as listed in Table 1, have been selected. These receivers were selected as the potentially worst affected receivers.

It is noted that other residential and non-residential sensitive receivers which could potentially be affected by the Proposal are also located in the vicinity of the Proposal, however as noted above, noise impacts have been assessed at the representative worst-affected receivers presented in Table 1.

**Table 1** Representative residential receiver addresses

Receiver ID	Receiver address
R1	70 MacIntosh Street, Mascot
R2	243-245 King Street, Mascot
R3	310 King Street, Mascot
R4	312 King Street, Mascot
R5	314 King Street, Mascot
R6	318 King Street, Mascot
R7	330 King Street, Mascot
N1	189 O'Riordan Street, Mascot
N2	154 O'Riordan Street, Mascot
N3	263 King Street, Mascot
N4	176 O'Riordan Street, Mascot
H1	205-209 O'Riordan Street, Mascot
H2	191 O'Riordan Street, Mascot




Figure 1 Proposal overview and sensitive receivers

## 2.3 Noise monitoring

Ambient noise monitoring was conducted at one location near the Proposal area during October 2019. This included both long term monitoring and short term attended measurements.

The unattended noise measurements define the long-term noise environment throughout the Proposal area and are used to define the construction noise management levels and the operational noise criteria. Attended noise measurements are carried out to determine what noise sources contribute to the local noise environment.

### 2.3.1 Instrumentation

Details of the equipment used for unattended long-term noise monitoring are presented in Table 2. The noise monitoring location is shown graphically in Figure 1.

**Table 2 Noise monitoring details**

Address	Model	Serial number
282 King Street, Mascot	Rion NL-52	876010

The sound level meter used to conduct attended measurements was a Bruel & Kjaer 2250 (Serial Number 3009329). All acoustic instrumentation used for the assessment comply with the requirements of AS IEC 61672.1-2004 Electroacoustics – Sound level meters – Specifications and were calibrated before and after monitoring sessions with a drift in calibration not exceeding  $\pm 0.5$  dB.

All instruments used were within their current National Association of Testing Authorities, Australia (NATA) certified in-calibration period (i.e. calibration in the last two years).

### 2.3.2 Unattended background noise monitoring results

Unattended noise monitoring was carried out from 18 October 2019 to 25 October 2019 at a location considered to be representative of the noise sensitive residential receivers near the Proposal area (refer to Figure 1).

A sound level meter measures the noise level over the sample period and then determines  $L_{A1}$ ,  $L_{A10}$ ,  $L_{A90}$ , and  $L_{Aeq}$  levels of the noise environment. The  $L_{A1}$ ,  $L_{A10}$  and  $L_{A90}$  levels are the levels exceeded for 1%, 10% and 90% of the sample period respectively. The  $L_{A1}$  is indicative of maximum noise levels due to individual noise events. The  $L_{A90}$  is considered to be the background noise level. The  $L_{Aeq}$  parameter is the energy averaged sound level over the measurement period. It is defined as the steady sound level that contains the same amount of acoustical energy as a given time-varying sound.

The assessment background level (ABL) is established by determining the lowest tenth-percentile level of the  $L_{A90}$  noise data acquired over each period of interest. The background noise level or rating background level (RBL) representing the day, evening and night-time assessment periods is based on the median of individual ABLs determined over the entire monitoring duration. The RBL is representative of the average minimum background sound level, or simply the background level.

A noise logger report including graphical representations of the logging results, a summary of the results and the measurement location is provided in Appendix B. A summary of the measured  $L_{A90}$  background noise levels and existing  $L_{Aeq}$  ambient noise levels is presented in Table 3.

**Table 3 Existing background and ambient noise levels, dB(A)**

Address	Rating background level, $L_{A90}$ , dB(A)			Ambient noise levels, $L_{Aeq}$ dB(A)		
	Day	Evening	Night	Day	Evening	Night
282 King Street, Mascot	46	42	37	65	64	58

Notes:

- In accordance with the NPfl, time of day is defined as follows:  
Day – the period from 7 am to 6 pm Monday to Saturday or 8 am to 6 pm on Sundays and public holidays.  
Evening – the period from 6 pm to 10 pm.  
Night – the remaining periods.

### 2.3.3 Attended noise monitoring

Attended noise monitoring was conducted on 25 October 2019. The measurement was completed over a 15 minute period. Weather conditions were clear on the day of monitoring, with negligible wind. The monitoring results from the attended measurements are presented in Table 4.

**Table 4** Attended noise monitoring details

Address	Date & time	Description	L <sub>Amax</sub> (15min) dB(A)	L <sub>A10</sub> (15min) dB(A)	L <sub>Aeq</sub> (15min) dB(A)	L <sub>A90</sub> (15min) dB(A)
282 King Street, Mascot	25/10/2019 10:41	Noise environment dominated by road traffic on King Street and aircraft take off noise. Helicopter flyover 63 dB (A).	85	58	55	46

## 3.0 Assessment criteria

### 3.1 Construction noise criteria

The *Interim Construction Noise Guideline* (ICNG) is a NSW Government document that identifies ways to manage impacts of construction noise on residences and other noise sensitive land uses. It is the principal guideline for the assessment and management of construction noise in NSW and is used to establish construction noise management levels (NML). As the proposed works are expected to continue for a period of more than three weeks and are within relatively close proximity to noise sensitive receivers, a quantitative assessment, based on 'reasonable' worst case construction scenarios, has been carried out for these works.

Noise levels resulting from construction activities are predicted at nearby noise sensitive receivers using noise modelling software and are compared to the levels provided in the *ICNG*. Where an exceedance of the noise management levels (NMLs) is predicted the *ICNG* advises that receivers can be considered 'noise affected' and the proponent should apply all feasible and reasonable work practices to minimise the noise impact. The proponent should also inform all potentially affected residents of the nature of the works to be carried out, the expected noise level and duration, as well as contact details should they wish to make a complaint.

Where construction noise levels at the receiver reach 75 dB(A) residential receivers are considered to be 'highly noise affected' and the proponent should, in consultation with the community, consider restrictions to the hours of construction to provide respite periods.

The *ICNG* defines what is considered to be feasible and reasonable as follows:

- Feasible - a work practice or abatement measure is feasible if it is capable of being put into practice or of being engineered and is practical to build given project constraints such as safety and maintenance requirements
- Reasonable - selecting reasonable measures from those that are feasible involves making a judgment to determine whether the overall noise benefits outweigh the overall adverse social, economic and environmental effects, including the cost of the measure.

Additionally, the *ICNG* notes that strong justification is required for work that is proposed outside of standard working hours.

Residential receiver NMLs for this Proposal have been derived using the information presented below in Table 5.

Table 5 Construction noise management levels – Residential receivers

Time of day	Construction noise management level $L_{Aeq,15min}$	How to apply
<p>Recommended standard hours:</p> <ul style="list-style-type: none"> <li>Monday to Friday 7am to 6pm</li> <li>Saturday 8am to 1pm</li> <li>No work on Sundays or public holidays</li> </ul>	Noise affected RBL + 10 dB(A)	<p>The noise affected level represents the point above which there may be some community reaction to noise.</p> <p>Where the predicted or measured <math>L_{Aeq,15 min}</math> is greater than the noise affected level, the proponent should apply all feasible and reasonable work practices to meet the noise affected level.</p> <p>The proponent should also inform all potentially impacted residents of the nature of works to be carried out, the expected noise levels and duration, as well as contact details.</p>
	Highly noise affected 75 dB(A)	<p>The highly noise affected level represents the point above which there may be strong community reaction to noise.</p> <p>Where noise is above this level, the relevant authority (consent, determining or regulatory) may require respite periods by restricting the hours that the very noisy activities can occur, taking into account:</p> <ul style="list-style-type: none"> <li>Times identified by the community when they are less sensitive to noise (such as before and after school for works near schools, or mid-morning or mid-afternoon for works near residences)</li> <li>If the community is prepared to accept a longer period of construction in exchange for restrictions on construction times.</li> </ul>
Outside recommended standard hours	Noise affected RBL + 5 dB(A)	<ul style="list-style-type: none"> <li>A strong justification would typically be required for works outside the recommended standard hours</li> <li>The proponent should apply all feasible and reasonable work practices to meet the noise affected level</li> <li>Where all feasible and reasonable practices have been applied and noise is more than 5 dB(A) above the noise affected level, the proponent should negotiate with the community</li> <li>For guidance on negotiating agreements see section 7.2.2 of the Interim Construction Noise Guideline.</li> </ul>

## Notes:

- Noise levels apply at the property boundary that is most exposed to construction noise, and at a height of 1.5 metres above ground level. If the property boundary is more than 30 metres from the residence, the location for measuring or predicting noise levels is at the most noise-affected point within 30 metres of the residence. Noise levels may be higher at upper floors of the noise affected residence.



### 3.1.1 Construction hours

The majority of work required for the Proposal would be carried out during standard construction hours as recommended in the ICNG as follows:

- 7:00am to 6:00pm Monday to Friday
- 8:00am to 1:00pm Saturdays
- No work on Sundays or public holidays.

Certain works may need to occur outside standard hours and would include night works and works during routine rail possessions. These are scheduled closures where part of the rail network is temporarily closed and trains are not operating. These would occur regardless of the Proposal.

Works are outside of standard hours required in some cases to minimise disruptions to customers, pedestrians, motorists and nearby sensitive receivers and to ensure the safety of railway workers and operational assets.

Out-of-hours works may also be scheduled outside routine scheduled closures. The construction contractor would require approval from TfNSW for any out-of-hours work. The affected community would be notified as outlined in TfNSW's *Construction Noise and Vibration Strategy (CNVS)*.

### 3.1.2 Construction noise management levels

Provided in Table 6 are the applicable NMLs for the Proposal, based on the RBLs in Table 3 and NMLs in Table 5.

**Table 6 Construction noise management levels - residential receivers**

Period	RBL $L_{A90}$ , dB(A)	Standard hours noise management levels, $L_{Aeq,15min}$ , dB(A)	Out-of-hours noise management levels, $L_{Aeq,15min}$ , dB(A)
Day	46	56	51
Evening	42	-	47
Night	37	-	42

NMLs recommended by the ICNG for non-residential sensitive land uses, such as schools, hospitals or places of worship are provided in Table 7. NMLs for commercial and industrial premises are provided in Table 8.

**Table 7 Construction noise management levels – non-residential sensitive land uses**

Land use	Management level, $L_{Aeq}(15 \text{ min})$
Classrooms at schools and other educational institutions	Internal noise level 45 dB(A)
Hospital wards and operating theatres	Internal noise level 45 dB(A)
Places of worship	Internal noise level 45 dB(A)
Active recreation areas (characterised by sporting activities and activities which generate their own noise or focus for participants, making them less sensitive to external noise intrusion)	External noise level 65 dB(A)
Passive recreation areas (characterised by contemplative activities that generate little noise and where benefits are compromised by external noise intrusion, for example, reading, meditation)	External noise level 60 dB(A)
Community centres	Depends on the intended use of the centre. Refer to the recommended “maximum” internal levels in AS2107 for specific uses.

**Table 8 Construction noise management levels – Commercial and industrial land uses**

Land use	Management level, $L_{Aeq}(15 \text{ min})$
Industrial premises	External noise level 75 dB(A)
Offices, retail outlets	External noise level 70 dB(A)

### 3.1.3 Sleep disturbance

The ICNG requires a sleep disturbance assessment to be undertaken where construction works are planned to extend over more than two consecutive nights. The ICNG makes reference to the EPA’s NSW *Environment Criteria for Road Traffic Noise* (ECRTN), now superseded by the NSW *Road Noise Policy* (RNP), for the assessment of sleep disturbance.

The guidance provided in the RNP for assessing the potential for sleep disturbance recommends that to minimise the risk of sleep disturbance during the night-time period (10pm to 7am), the  $L_{A1}(1 \text{ min})$  noise level outside a bedroom window should not exceed the  $L_{A90}(15 \text{ min})$  background noise level by more than 15 dB(A). The EPA considers it appropriate to use this metric as a screening criterion to assess the likelihood of sleep disturbance. If this screening criterion is found to be exceeded then a more detailed analysis must be undertaken that should include the extent that the maximum noise level exceeds the background noise level and the number of times this is likely to happen during the night-time period.

The RNP contains a review of research into sleep disturbance which represents NSW EPA advice on the subject of sleep disturbance due to noise events. It concludes that having considered the results of research to date that, “*Maximum internal noise levels below 50-55 dB(A) are unlikely to cause awakening reactions*”. Therefore, given that an open window provides around 10 dB(A) in noise attenuation from outside to inside, external noise levels of 60-65 dB(A) are unlikely to result in awakening reactions.

Table 9 presents the sleep disturbance screening and sleep disturbance awakening reaction criteria.

**Table 9 Construction noise sleep disturbance criteria**

Night-time rating background level, dB(A)	Sleep disturbance screening $L_{A1(1min)}$ criteria, dB(A)	Sleep disturbance awakening reaction $L_{A1(1min)}$ criteria, dB(A)
37	52	65

### 3.1.4 Construction road traffic noise

Noise from construction traffic on public roads is not covered by the ICNG. However, the ICNG does refer to the *Environment Criteria for Road Traffic Noise*, which is now superseded by the RNP, for the assessment of noise arising from construction traffic on public roads.

To assess noise impacts from construction traffic, an initial screening test has been undertaken by evaluating whether existing road traffic noise levels would increase by more than 2 dB(A). Where the predicted noise increase is 2 dB(A) or less, then no further assessment is required. However, where the predicted noise level increase is greater than 2 dB(A), and the predicted road traffic noise level exceeds the road category specific criterion then noise mitigation should be considered for those receivers affected. The RNP does not require assessment of noise impact to commercial or industrial receivers.

## 3.2 Construction vibration criteria

The relevant standards/guidelines for the assessment of construction vibration are summarised in Table 10.

**Table 10 Standards/guidelines used for assessing construction vibration**

Item	Standard/guideline
Structural damage	German Standard DIN 4150 – Part 3 – <i>Structural Vibration in Buildings – Effects on Structures</i> (DIN 4150)
Human comfort (tactile vibration)	<i>Assessing Vibration: A Technical Guideline</i> (AVATG) <sup>1</sup>

Notes:

- This document is based upon the guidelines contained in British Standard 6472:1992, "Evaluation of human exposure to vibration in buildings (1-80 Hz)". This British Standard was superseded in 2008 with BS 6472-1:2008 "Guide to evaluation of human exposure to vibration in buildings – Part 1: Vibration sources other than blasting" and the 1992 version of the Standard was withdrawn. Although a new version of BS 6472 has been published, the Environment Protection Authority still requires vibration to be assessed in accordance with the 1992 version of the Standard at this point in time.

Vibration, at levels high enough, has the potential to cause damage to structures and disrupt human comfort. Vibration and its associated effects are usually classified as continuous, impulsive or intermittent as follows:

- continuous vibration continues uninterrupted for a defined period and includes sources such as machinery and continuous construction activities
- impulsive vibration is a rapid build up to a peak followed by a damped decay. It may consist of several cycles at around the same amplitude, with durations of typically less than two seconds and no more than three occurrences in an assessment period. This may include occasional dropping of heavy equipment or loading activities
- intermittent vibration occurs where there are interrupted periods of continuous vibration, repeated periods of impulsive vibration or continuous vibration that varies significantly in magnitude. This may include intermittent construction activity, impact pile driving, jack hammers.

### 3.2.1 Structural damage

At present, no Australian Standards exist for the assessment of building damage caused by vibration.

The German standard (DIN 4150) provides recommended maximum levels of vibration that reduce the likelihood of building damage caused by vibration and are presented in Table 11. DIN 4150 states that

buildings exposed to higher levels of vibration than recommended limits would not necessarily result in damage.

**Table 11 Structural damage safe limits for building vibration (Vibration peak particle velocity)**

Group	Type of structure	At foundation - Less than 10 Hz	At foundation - 10 Hz to 50 Hz	At foundation - 50 Hz to 100 Hz <sup>1</sup>	Vibration at the horizontal plane of the highest floor for all frequencies
1	Buildings used for commercial purposes, industrial buildings and buildings of similar design	20 mm/s	20 to 40 mm/s	40 to 50 mm/s	40 mm/s
2	Dwellings and buildings of similar design and/or use	5 mm/s	5 to 15 mm/s	15 to 20 mm/s	15 mm/s
3	Structures that because of their particular sensitivity to vibration, do not correspond to those listed in Lines 1 or 2 and have intrinsic value (e.g. buildings that are under a preservation order/heritage listed)	3 mm/s	3 to 8 mm/s	8 to 10 mm/s	8 mm/s

Notes:

1. At frequencies above 100 Hz, the values given in this column may be used as minimum values

### 3.2.2 Human comfort

The assessment of intermittent vibration outlined in the NSW EPA guideline *Assessing Vibration: A Technical Guideline* is based on Vibration Dose Values (VDVs). The VDV accumulates the vibration energy received over the daytime and night-time periods.

Maximum and preferred VDVs for intermittent vibration arising from construction activities are listed in Table 12. The VDV criteria are based on the likelihood that a person would be annoyed by the level of vibration over the entire assessment period.

**Table 12 Preferred and maximum vibration dose values for intermittent vibration (m/s<sup>1.75</sup>)**

Location	Daytime <sup>1</sup> Preferred	Daytime Max	Night time Preferred	Night time Max
Critical areas <sup>2</sup>	0.10	0.20	0.10	0.20
Residences	0.20	0.40	0.13	0.26
Offices, schools, educational institutions and places of worship	0.40	0.80	0.40	0.80
Workshops	0.80	1.60	0.80	1.60

Notes:

1. Day is defined as 7:00 am to 10:00 pm. Night is defined as 10:00 pm to 7:00 am
2. Examples include hospital operating theatres and precision laboratories where sensitive operations are occurring. These criteria are only indicative, and there may be a need to assess intermittent values against continuous or impulsive criteria for critical areas.

### 3.3 Operational noise criteria

The EPA's *Noise Policy for Industry* (NPfI) provides noise trigger levels for assessing the potential impact of noise from industry and includes a framework for considering feasible and reasonable noise mitigation measures. The assessment procedure for industrial noise sources has two components that must be considered:

- controlling intrusive noise impacts in the short term for residences
- maintaining noise level amenity for residences and other land uses.

#### 3.3.1 Intrusiveness noise levels

The NPfI states that the intrusiveness of an industrial noise source may generally be considered acceptable if the level of noise from the source ( $L_{Aeq}$  level), measured over a 15 minute period, does not exceed the RBL measured by more than 5 dB(A). The RBL is the background noise level to be used for assessment purposes and is determined by the methods given in Fact Sheet B of the NPfI. Adjustments are to be applied to the level of noise produced if the noise at the receiver contains annoying characteristics such as tonality or impulsiveness.

The intrusiveness noise levels applicable to the Proposal are presented in Table 13.

**Table 13 Intrusiveness noise levels**

Period	RBL. $L_{A90}$ , dB(A)	Intrusiveness noise level (RBL + 5), dB(A)
Day	46	51
Evening	42	47
Night	37	42

Notes:

1. In accordance with the NPfI, time of day is defined as follows:  
Day – the period from 7 am to 6 pm Monday to Saturday or 8 am to 6 pm on Sundays and public holidays.  
Evening – the period from 6 pm to 10 pm.  
Night – the remaining periods.

#### 3.3.2 Protecting noise amenity

To limit continuing increase in noise levels, the maximum ambient noise level within an area from all industrial noise sources should not normally exceed the acceptable noise levels specified in Table 2.2 of the NPfI. That is the noise level should not exceed the level appropriate for the particular locality and land use. This is often termed the “background creep” or “amenity criterion”.

The recommended amenity noise levels represent the objectives for total industrial noise at a receiver location, whereas the project amenity level represents the objective for noise from a single industrial

development at a receiver location. The project amenity level is calculated by subtracting 5 dB(A) from the recommended amenity noise level.

Where high levels of transport noise may be high enough to make noise from an industrial source effectively inaudible the project amenity noise level is equal to the  $L_{Aeq,period(traffic)}$  recommended amenity level.

It was observed during attended and unattended noise monitoring that:

- road traffic noise from King Street and aircraft noise were the dominant source of noise
- the existing  $L_{Aeq,period}$  traffic noise level is 10 dB(A) or more above the amenity noise level for some receiver types
- it is unlikely that traffic noise will reduce over time.

Therefore, the high traffic noise provisions were applied in accordance with the NPfI, Section 2.4.1 for some receiver types during the evening and night time periods.

In addition, the project amenity level is converted from a period to 15 minutes by adding 3 dB(A).

The project amenity noise levels applicable to the Project are provided in Table 14.

**Table 14 Recommended  $L_{Aeq}$  noise levels from industrial noise sources**

Type of receiver	Period	Recommended amenity noise level, dB(A)	Project amenity noise amenity level, dB(A)	
		$L_{Aeq(period)}$	$L_{Aeq(15min)}$	$L_{Aeq(15min)}$
Residential Urban	Day	60	55	58
	Evening	50	49	52 <sup>1</sup>
	Night	45	43	46 <sup>1</sup>
Hotel, motels, caretakers' quarters, holiday accommodation, permanent resident caravan parks	Day	65	60	63
	Evening	55	50	53
	Night	50	45	48
School classroom	Noisiest 1-hour period when in use	45 <sup>2</sup>	45	48
School playground	When in use	55	55	58
Area specifically reserved for passive recreation (e.g. national park)	When in use	50	50	53
Place of worship	When in use	50 <sup>2</sup>	50	53
Commercial premises	When in use	65	65	68

Notes:

1. The existing  $L_{Aeq,period}$  traffic noise level is 10 dB(A) or more above the applicable recommended amenity noise level. Therefore, the high traffic noise provisions were applied in accordance with the NPfI, Section 2.4.1, based on existing  $L_{Aeq}$  levels presented in Table 3
2. External noise levels are based on a 10 dB(A) reduction from outside to inside through an open window.

The project noise trigger level is the lower of the intrusiveness (Table 13) and the amenity noise levels (Table 14). Provided in Table 15 are the established project noise trigger levels for the assessment locations within the Proposal area. Table 15 presents the project noise trigger levels for the day, evening and night-time periods.

**Table 15 Operational noise criteria**

Type of receiver	Assessment period	Intrusive noise levels, $L_{Aeq,15min}$	Amenity noise levels, $L_{Aeq,15min}$	Project noise trigger levels, $L_{Aeq,15min}$
Residential suburban	Day	51	58	51
	Evening	47	52	47
	Night	42	46	42
Hotel, motels, caretakers' quarters, holiday accommodation, permanent resident caravan parks	Day	-	63	63
	Evening	-	53	53
	Night	-	48	48
School classroom	Noisiest 1-hour period when in use	-	48	48
School playground	When in use	-	58	58
Area specifically reserved for passive recreation (e.g. national park)	When in use	-	53	53
Place of worship - internal	When in use	-	53	53
Commercial premises	When in use	-	68	68

### 3.3.3 Tonality

The NPfl requires a penalty for noise characteristics such as tonality, impulsiveness, intermittency, irregularity or low frequency content. Specifically, the penalty is *"to be applied to the noise from the source predicted at the receiver"*. Modifying factor corrections have been assessed in accordance with Factsheet C of the NPfl.

The NPfl provides additional guidance and criteria for assessing noise emission from sources defined as 'tonal' or 'low-frequency'. Of significance to substation noise is that penalties of up to 5 dB(A) may be applied where the subject noise emission is tonal or has significant low frequency content at the receiver.

#### Tonal noise

A tonal penalty is applied when the level of a one-third octave band exceeds the level of each adjacent band by:

- 5 dB(A) or more if the centre frequency of the band containing the tone is between 500 Hz and 10,000 Hz;
- 8 dB(A) or more if the centre frequency of the band containing the tone is between 160 Hz and 400 Hz;

- 15 dB(A) or more if the centre frequency of the band containing the tone is between 25 Hz and 125 Hz;

### Low frequency noise

A low frequency noise penalty is applied when the difference between the C and A weighted noise levels is 15 dB or more and:

- where any of the one-third octave noise levels in Table 16 are exceeded by up to and including 5 dB and cannot be mitigated, a 2 dB(A) positive adjustment to measured/predicted A-weighted levels applies for the evening/night period
- where any of the one-third octave noise levels in Table 16 are exceeded by more than 5 dB and cannot be mitigated, a 5 dB(A) positive adjustment to measured/predicted A-weighted levels applies for the evening/night period and a 2 dB(A) positive adjustment applies for the daytime period.

**Table 16 One-third octave low-frequency noise thresholds**

Hz/dB (Z)	One-third octave $L_{Zeq(15\ min)}$ threshold level												
Frequency (Hz)	10	12.5	16	20	25	31.5	40	50	63	80	100	125	160
dB(Z)	92	89	86	77	69	61	54	50	50	48	48	46	44

The maximum adjustment is 10 dB(A) where the noise contains two or more modifying factors (excluding the duration correction).

The tonal characteristics of the proposed equipment should be considered at the detailed design stage.

### 3.3.4 Maximum noise level assessment

The NPfl requires the potential for sleep disturbance to be assessed by considering maximum noise levels events during the night-time period.

Where the subject development night-time noise levels at a residential location exceed the following screening levels a detailed maximum noise level event assessment should be undertaken:

- $L_{Aeq(15min)}$  40 dB(A) or the prevailing RBL plus 5 dB, whichever is the greater, and/or
- $L_{AFmax}$  52 dB(A) or the prevailing RBL plus 15 dB, whichever is the greater,

The detailed assessment should cover the maximum noise level, the extent to which the maximum noise level exceeds the rating background noise level, and the number of times this happens during the night-time period.

Based on the measured background noise levels during the night, the sleep disturbance criteria for the nearest noise sensitive residential receivers are presented in Table 17.

**Table 17 Night-time sleep disturbance screening levels**

Type of receiver	Measured night-time RBL, $L_{A90,15min}$ , dB(A)	Sleep disturbance screening levels	
		$L_{Aeq(15min)}$ , dB(A)	$L_{AFmax}$ , dB(A)
Residential	37	42	52



## 4.0 Construction noise assessment

### 4.1 Construction stages and scheduling

Construction activities to be carried out as part of the Proposal are outlined in Table 18. The work has been grouped into five distinct construction stages based on proposed construction activities.

Certain work may need to occur outside standard construction hours. This has been discussed further in Section 3.1.1. In the absence of information regarding which activities are proposed to occur outside of standard construction hours, this assessment has considered all scenarios to be conducted both during standard construction hours and out-of-hours.

**Table 18 Proposed construction activities**

Construction stage	Activities
Site establishment and enabling works	<ul style="list-style-type: none"> <li>establishment of site compound and temporary facilities at 166 O’Riordan Street (i.e. erect fencing, site offices, temporary toilets, hoarding, amenities and plant/material storage areas)</li> <li>installation of construction road signage as per Traffic Management Plan (TMP)</li> <li>clearing of vegetation from works area, where possible</li> <li>installation of environmental controls (i.e. erosion and sediment control fencing)</li> </ul>
New Mascot Substation	<ul style="list-style-type: none"> <li>subgrade preparation for pavement</li> <li>excavation and drainage works</li> <li>construct new substation building</li> <li>fit out substation building, including installation of electrical components (i.e. lighting, CCTV, PA system, etc.)</li> <li>installation of boundary fencing and removable gate to O’Riordan Street</li> <li>installation of conduits for cables</li> <li>line-marking for light vehicle parking</li> <li>construction of the new driveway with a suitable turning radius and associated works such as kerb and gutters</li> </ul>
Testing and commissioning	<ul style="list-style-type: none"> <li>testing electrical, communications and signalling components</li> </ul>
Demobilisation	<ul style="list-style-type: none"> <li>remove temporary site fencing</li> <li>dismantling of temporary site compounds/hoarding areas</li> <li>remove temporary construction signage.</li> </ul>

### 4.2 Plant and equipment levels

Presented in Table 19 are the typical sound power levels of the construction equipment to be used during each modelled construction scenario. The modelled scenarios include all equipment that could be reasonably assumed to be operating at the same time for an entire 15 minute period.

These sound power levels are typical values taken from data provided in Australian Standard AS2436-2010 *Guide to noise and vibration control on construction, demolition and maintenance sites* and British Standard 5228: Part 1 2009 *Code of practice for noise and vibration control on construction and open sites*, 2009 as well as AECOM’s noise database.

These sound power levels assume equipment is modern and in good working order. In AECOM’s experience,  $L_{A1}$  sound power levels of construction activities are typically up to eight decibels above  $L_{Aeq}$  sound power levels.

For the noise assessment only the worst case construction scenarios have been considered (shaded blue in Table 19). These scenarios were chosen based not only on their overall sound power level, but also their location within the Proposal boundary.

During the detailed design local site conditions and changes in work practices may cause some variation in the equipment used. While the equipment may vary, other major infrastructure projects have shown that due to the conservative approach to noise predictions, received noise levels are unlikely to be appreciably higher than those predicted in this assessment.

This approach is used at this point in the assessment to ensure that identified impacts are not under-predicted and adequate noise management and mitigation measures are considered early in the Proposal.

**Table 19 Construction staging and typical sound power levels of construction equipment (modelled scenarios – blue)**

Construction stage	Equipment	Sound power level, dB(A)
Site establishment and enabling works	Bobcat	104
	Generator	101
	Hand tools	98
	Lighting tower	95
	Light vehicles	90
	Trucks	98
	<b>Total</b>	<b>107</b>
New Substation construction	8t Excavator	99
	Franna crane	93
	Hand tools	98
	Generator	101
	35t Piling rig	103
	Trucks	98
	Concrete pump	105
	Agitator	109
	<b>Total</b>	<b>112</b>
Testing and commissioning	Hand tools	98
	Lighting tower	95
	Trucks	98
	Light vehicles	90
	<b>Total</b>	<b>102</b>
Demobilisation	Bobcat	104
	Generator	101
	Hand tools	98
	Light vehicles	90

Construction stage	Equipment	Sound power level, dB(A)
	Lighting tower	95
	Trucks	98
	<b>Total</b>	<b>107</b>

### 4.3 Noise modelling methodology

Noise levels due to the construction activities shown in Table 19 were predicted at nearby noise sensitive receivers using SoundPLAN v8.0 noise modelling software. The noise model was created to represent 'reasonable' worst periods of construction work. The noise model included all sensitive residential and non-residential receivers within a reasonable distance of the construction activities.

The following features were included in the noise model:

- ground topography
- ground absorption and reflection
- receivers as shown in Figure 1
- construction noise sources as outlined in Table 19.

Noise emissions from the construction sites have been modelled using an implementation of the ISO 9613-2:1996 propagation algorithm with neutral meteorological conditions.

It can be expected that there may be differences between predicted and measured noise levels due to variations in instantaneous operating conditions, plant in operation during the measurement and also the location of the plant equipment.

#### 4.3.1 Construction modelling assumptions

The following assumptions were made in modelling the construction noise scenarios:

- all equipment would be operating simultaneously, which is unlikely and hence a conservative assumption
- equipment was assumed to be operating at the closest point in the Proposal area to each receiver, in order to present the worst-case scenario
- neutral atmospheric conditions i.e. relatively calm, no wind.

### 4.4 Predicted construction noise impacts

A summary of the number of receivers where construction noise levels are predicted to exceed NMLs during the loudest construction stages are presented for standard hours construction activities in Table 20 and for out-of-hours construction activities in Table 21. Out-of-hours work has been conservatively assessed against the more stringent night-time criteria. Appendix C presents the  $L_{Aeq}$  noise level contours.

It is important to consider that this assessment is representative of the worst case 15 minute period of construction activity, while the construction equipment is at the nearest location to each sensitive receiver location. The assessed scenario does not represent the ongoing day to day noise impact at noise sensitive receivers for an extended period of time.

Particularly noisy activities are likely to persist for only a portion of the overall construction period. In addition, the predictions use the shortest separation distance to each sensitive receiver, however in reality the distance will vary between plant and sensitive receivers.

**Table 20 Predicted construction noise impacts for residential receivers - Daytime**

Construction scenario	NML	Number of receivers where noise levels >10 dB(A) above NML	Number of highly noise affected receivers where noise levels ≥75 dB(A)
Site establishment	56	0	0
New substation construction	56	0	0

**Table 21 Predicted construction noise impacts for residential receivers – Night-time**

Construction scenario	NML	Number of receivers where noise levels may exceed the NML			
		NML exceedance <5 dB(A)	NML exceedance 5-14 dB(A)	NML exceedance 15-25 dB(A)	NML exceedance >25 dB(A)
Site establishment	42	7	1	0	0
New substation construction	42	31	8	0	0

The results presented in Table 20 show that there is a very limited number of exceedances of the NMLs adopted in Section 3.1. During standard daytime construction hours, there are no receivers where noise levels are anticipated to exceed the NMLs by more than 10 dB(A), and no receivers are expected to be considered highly noise affected (>75 dB(A)).

The results presented in Table 21 show that during the night-time, noise levels at a number of receivers are predicted to exceed the NMLs. Noise levels at up to 39 receivers are predicted to exceed the NMLs in the worst-case scenario – new substation construction. This is due to the high noise levels associated with this activity, proximity to noise sensitive receivers, in addition to the lower NMLs applicable during the night-time.

Recommendations to mitigate construction noise impacts have been provided in Section 7.0.

## 4.5 Sleep disturbance assessment

Sleep disturbance is assessed using an  $L_{A1(1\text{min})}$  parameter, which is considered to be the maximum noise level excluding extraneous noise events. A sleep disturbance assessment has been undertaken for the proposed night works with the construction information available to date. The noise modelling results are provided in Table 22 below with predicted noise levels compared with the sleep awakening reaction criterion.

**Table 22 Predicted  $L_{A1(1\text{min})}$  sleep disturbance impacts at residential receivers**

Construction scenario	Sleep disturbance criteria, dB(A)	Maximum $L_{A1(1\text{min})}$ noise level, dB(A)	Number of receivers where noise levels exceed	
			Sleep disturbance criteria	Awakening reaction criteria
Site establishment	52	63	8	0
New substation construction	52	64	25	0

A number of exceedances of the sleep disturbance screening criteria have been predicted due to the potential night-time construction works associated with the Proposal. However, noise associated with construction works are not anticipated to exceed the awakening reaction criteria.

#### 4.6 Construction traffic assessment

For the construction traffic noise assessment indicative construction vehicle movements have been used in the absence of detailed vehicle movements.

Traffic counts for the existing AM peak (8am – 9am) and PM peak (5pm – 6pm) traffic flows have been sourced from a survey in a previous assessment completed for the Airport North Precinct titled 'Westconnex enabling works (North) O'Riordan Street/Robey Street REF' dated August 2015. These values have been converted to daytime (15 hour) and night-time (9 hour) traffic volumes. This conversion assumed the peak hour traffic flow is 11 per cent of the daily 24 hour traffic volume, and 88 per cent of the daily 24 hour traffic volume occurs during the 15 hour day (7am to 10pm) period whilst the remaining 12% of vehicles travel during the 9 hour night-time (10pm to 7am) period. These volumes are presented in Table 23 below. The traffic study also provided future traffic increases, however the existing survey has been used as it represents a conservative assessment.

It has also been assumed that current traffic consists of 7 per cent heavy vehicles during the daytime and night-time.

The following construction traffic movements were conservatively used:

- 70 light vehicle movements during the daytime and night-time periods
- 30 heavy vehicle movements during the daytime and night-time periods.

**Table 23 Existing traffic flows and additional traffic flows due to construction traffic**

Road	Period	Existing traffic flow		Additional traffic flow		Relative noise increase, dB(A)
		Light	Heavy	Light	Heavy	
O'Riordan Street, Mascot	Daytime	23,205	1,747	70	30	0.0
	Night-time	3,164	238	70	30	0.3

The results indicate that the predicted noise increases are expected to be lower than the 2 dB(A) screening criteria presented in the RNP. As a result, no further consideration of construction traffic is required at this stage.

## 5.0 Construction vibration assessment

Vibration intensive work has the potential to occur as part of the construction work. Work may include the use of jackhammers and a bored piling rig.

Typical minimum distances for the construction equipment that may be part of this Proposal are provided in Table 24. Minimum working distances have been developed to meet the recommended levels of vibration in British Standard 6472-1992 and DIN 4150, and are based upon the safe working distances presented in TfNSW's CNVS and AECOM's library of vibration data.

Minimum working distances should be adhered to when operating vibration intensive equipment near buildings in order to minimise the risk of discomfort to occupants and structural damage.

**Table 24 Recommended minimum working distances for vibration intensive equipment**

Equipment	Rating/description	Minimum working distance (metres)	
		Cosmetic damage <sup>1</sup>	Human response
Piling rig – bored	≤ 800 mm	2 (nominal)	N/A
Jackhammer	Hand held	1 (nominal)	Avoid contact with structure

Notes:

1. More stringent conditions may apply to heritage or other sensitive structures

The minimum working distances presented in Table 24 assume individual items of plant would be operating independently. Concurrent operation of vibration intensive equipment should be avoided, however if it is necessary to operate multiple items of equipment concurrently close to the safe working distance then vibration monitoring is recommended.

The minimum working distances for cosmetic damage are generally considered to be conservative and working within them would not necessarily result in damage. However, factors such as work practices and intervening ground conditions can affect vibration levels so vibration monitoring is recommended within these distances and should be carried out at the beginning of the work in order to refine the safe working distances for site specific conditions.

A discussion of vibration mitigation is provided in Section 7.0.

## 6.0 Operational noise assessment

### 6.1 Assessment overview

Noise emissions associated with the operation of the new substation were assessed in accordance with the NPfl.

Noise levels were predicted at nearby receiver locations based on typical operational noise sources from similar substation facilities. The typical scenarios were modelled to assess the potential for noise emissions to impact nearby sensitive receiver locations and achieve the required project noise trigger levels presented in Section 3.3. The predicted noise levels are presented in Section 6.4 for 'reasonable' worst case night-time operations.

### 6.2 Noise modelling methodology

The operational noise levels were predicted using an implementation of CONCAWE<sup>1</sup> algorithms in the SoundPLAN v8.0 noise propagation software.

#### 6.2.1 Meteorological conditions

Both standard and noise-enhancing meteorological conditions were considered in accordance with the NPfl, with the following parameters:

##### Night-time

- standard meteorological conditions – Pasquill stability class D with wind speed up to 0.5 m/s at 10 metres
- noise-enhancing meteorological conditions – Pasquill stability class D with wind speed up to 3 m/s at 10 metres, and/or stability category F with winds up to 2 m/s at 10 metres.

The modelling includes:

- ground topography
- buildings and structures
- all identified noise producing items within the Proposal site modelled as point or line sources where appropriate
- all sources are modelled to assume a 'reasonable' worst case 15-minute period scenario
- ground absorption.

It can be expected that there may be differences between predicted and measured noise levels due to variations in instantaneous operating conditions, plant in operation during the measurement and also the location of the equipment and other noise sources.

All predicted noise levels are free field and at the most-affected point within a residential property boundary within 30 m of the nearest facade.

### 6.3 Noise sources modelled

This section discusses the assumed sources of noise emission from the Proposal. The operational equipment are generally categorised as steady-state or quasi steady-state noise sources which typically produce continuous and consistent noise levels. The operation of the substation equipment is expected to be consistent throughout the daytime, evening and at night.

To undertake the operational noise assessment in accordance with the NPfl, the future operations were considered for the night-time periods. This scenario has been assumed to represent 'reasonable' worst case operational conditions.

---

<sup>1</sup> CONCAWE – The oil companies' international study group for conservation of clean air and water – Europe (established in 1963) Report 4/81 "The propagation of noise from petroleum and petrochemical complexes to neighbouring communities".

The major noise sources that have been considered for the operation of the new substation are detailed in Table 25.

**Table 25 Substation equipment reference noise levels**

Source	Sound power level (SWL), dB(A)
5.35 MVA Rectifier Transformer	68 L <sub>Aeq</sub> <sup>1</sup>
Reactor	71 L <sub>Aeq</sub> <sup>2</sup>
9.25 MVA Transformer	72 L <sub>Aeq</sub> <sup>1</sup>
Auxiliary Transformer	48 L <sub>Aeq</sub> <sup>1</sup>

Notes:

- 1 Sound Power Level (SWL) calculated in accordance with reduced maximum noise levels provided in AS60076.10.1:2009 considering the transformer capacity.
- 2 SWL based on equipment on similar substations projects.

The noise generating equipment and the equipment sound power levels should be confirmed at the detailed design stage.

### 6.3.1 Maximum Noise levels

As stated above, the operational equipment are generally categorised as steady-state or quasi steady-state noise sources which typically produce continuous and consistent noise levels.

In AECOM's experience, L<sub>A1</sub> sound power levels of substation equipment are typically not greater than five decibels above L<sub>Aeq</sub> sound power levels. Given that the L<sub>A1</sub> sleep disturbance criterion is 10 dB less stringent than the project noise trigger level, compliance with the project noise trigger level will result in compliance with the sleep disturbance criteria. Therefore, no further consideration has been given to the sleep disturbance assessment.

## 6.4 Noise modelling results

### 6.4.1 L<sub>Aeq</sub> noise levels

A summary of the predicted operational noise impacts associated with the operations of the Proposal is presented for the night-time in Table 26. A graphical presentation of results is shown in Appendix D.



**Table 26 Summary of predicted noise levels for night time operations**

Receiver location	Project noise trigger level, dB(A)	Predicted L <sub>Aeq</sub> noise level, dB(A)	
		Standard meteorological conditions	Noise-enhancing meteorological conditions
R1 - 70 MacIntosh Street, Mascot	42	16	17
R2 - 243-245 King Street, Mascot	42	11	12
R3 - 310 King Street, Mascot	42	18	18
R4 - 312 King Street, Mascot	42	22	22
R5 - 314 King Street, Mascot	42	25	25
R6 - 318 King Street, Mascot	42	24	24
R7 - 330 King Street, Mascot	42	36	36
N1 - 189 O'Riordan Street, Mascot	63	47	47
N2 - 154 O'Riordan Street, Mascot	63	38	38
N3 - 263 King Street, Mascot	63	36	36
N4 - 176 O'Riordan Street, Mascot	63	52	52
H1 - 205-209 O'Riordan Street, Mascot	48	45	45
H2 - 191 O'Riordan Street, Mascot	48	46	48

As stated in Section 3.3.3, the maximum adjustment for annoying characteristics is 10 dB(A) where the noise contains two or more modifying factors (excluding the duration correction). Based on spectral noise levels for typical transformers, the proposed substation may be tonal and therefore attract a 5 dB adjustment. The predicted noise levels in Table 26 include the 5 dB tonality adjustment.

The tonal characteristics of the proposed equipment should be reviewed at the detailed design stage.

Considering tonality adjustment, it can be seen in Table 26 that the noise levels are not predicted to exceed the project noise trigger level at any of the selected representative receivers. It is likely that the noise emission from the Proposal will also comply at receivers at greater distances.

## 7.0 Mitigation measures

### 7.1 Construction noise and vibration mitigation

This section of the report presents construction noise and vibration mitigation measures to be considered for implementation to minimise and manage construction noise impacts.

The construction noise assessment presented in Section 4.0 of this report detailed a number of exceedances of the NMLs within the Proposal area. These were predicted as a result of various different construction activities. The following generic and receiver specific mitigation measures have been identified.

#### 7.1.1 Construction Noise and Vibration Management Plan

A Construction Noise and Vibration Management Plan (CNVMP) should be developed for the Proposal and implemented prior to commencement of construction activities. The CNVMP should include all feasible and reasonable safeguards to manage the noise emissions from the site and any complaints which may occur due to construction noise. The CNVMP should include, as a minimum, the following:

- identification of nearby residences and other sensitive land uses
- description of approved hours of work
- description and identification of all construction activities, including work areas, equipment and duration
- description of what work practices (generic and specific) would be applied to minimise noise and vibration
- a complaints handling process
- noise and vibration monitoring procedures, including for heritage structures
- overview of community consultation required for identified high impact works.

Construction works should be planned and carried out during standard construction hours wherever possible. Table 27 presents the standard mitigation measures contained within the *Construction Noise and Vibration Strategy* (CNVS) which should be considered as mitigation measures as part of the CNVMP.

**Table 27 Transport for NSW's CNVS standard mitigation measures**

Action required	Safeguard details
<b>Management measures</b>	
Implement any project specific mitigation measures required	In addition to the measures set out in this table, any project specific mitigation measures identified in this report.
Implement stakeholder consultation measures	Periodic notification (monthly letterbox drop and website notification) detailing all upcoming construction activities will be delivered to sensitive receivers at least seven days prior to commencement of relevant works.
Site inductions	All employees, contractors and subcontractors will receive an environmental induction.
Behavioural practices	No swearing or unnecessary shouting or loud stereos/radios on site. No dropping of materials from height, throwing of metal items or slamming of doors.

Action required	Safeguard details
Noise monitoring	<p>A noise monitoring program will be implemented to assist in confirming and controlling the site specific potential for disturbance at particularly sensitive localities at the commencement of activities and periodically during the construction program as the works progress. The program will be developed in accordance with the CNVMP and any approval/licence conditions.</p> <p>The results will be reviewed to determine if additional mitigation measures are required. All measurements will be undertaken in accordance with Australian Standard 1055.2018 – <i>Acoustics – Description and measurement of environmental noise</i>.</p>
<b>Source controls</b>	
Construction hours and scheduling	Where feasible and reasonable, construction will be carried out during the standard daytime working hours. Should out-of-hours works be required an out-of-hours works application form will be submitted to TfNSW for approval on a case-by-case basis. Work generating high noise and/or vibration levels will be scheduled during less sensitive time periods as far as practicable. This will potentially include the use breakers and jackhammers.
Construction respite period	<p>Noise with special audible characteristics and vibration generating activities (including jack hammering) will only be carried out in continuous blocks, not exceeding three hours each, with a minimum respite period of one hour between each block.</p> <p>'Continuous' includes any period during which there is less than a one hour respite between ceasing and recommencing any of the work. No more than two consecutive nights of noise with special audible characteristics and/or vibration generating work will be undertaken in the same area over any seven day period, unless otherwise approved by the relevant authority.</p>
Equipment selection	<p>Quieter and less vibration emitting construction methods will be used where feasible and reasonable (e.g. rubber wheeled instead of steel tracked plant).</p> <p>Equipment will be regularly inspected and maintained to ensure it is in good working order.</p>
Maximum noise levels	The noise levels of plant and equipment will have operating sound power or sound pressure levels that would meet the predicted noise levels.
Rental plant and equipment	Noise emissions will be considered as part of the selection process.
Use and siting of plant	<ul style="list-style-type: none"> <li>• Simultaneous operation of noisy plant within discernible range of a sensitive receiver will be avoided.</li> <li>• The offset distance between noisy plant and adjacent sensitive receivers will be maximised.</li> <li>• Plant used intermittently will be throttled down or shut down.</li> <li>• Plant and vehicles will be turned off when not in use.</li> <li>• Noise-emitting plant will be directed away from sensitive receivers where reasonable and feasible.</li> </ul>

Action required	Safeguard details
Plan work site and activities to minimise noise and vibration	<p>Traffic flow, parking and loading/unloading areas will be planned to minimise reversing movements within the site.</p> <p>Truck drivers will be advised of designated vehicle routes, parking locations, acceptable delivery hours or other relevant practices (i.e. minimising the use of engine brakes, and no extended periods of engine idling).</p>
Non-tonal reversing alarms	Non-tonal reversing beepers (or an equivalent mechanism) will be fitted and used on all construction vehicles and mobile plant regularly used on site and for any out-of-hours work.
Minimise disturbance arising from delivery of goods to construction sites	<ul style="list-style-type: none"> <li>• Loading and unloading of materials/deliveries will occur as far as possible from sensitive receivers.</li> <li>• Site access points and roads will be selected as far as possible away from sensitive receivers.</li> <li>• Dedicated loading/unloading areas will be shielded if close to sensitive receivers.</li> <li>• Delivery vehicles will be fitted with straps rather than chains for unloading, wherever possible.</li> </ul>
Silencers on mobile plant	<p>Where possible noise from mobile plant will be reduced through additional fittings including:</p> <ul style="list-style-type: none"> <li>• residential grade mufflers</li> <li>• silenced air parking brake engagement.</li> </ul>
Construction related traffic	<p>Vehicle movements will be routed away from sensitive receivers and scheduled during less sensitive times.</p> <ul style="list-style-type: none"> <li>• The speed of vehicles will be limited and the use of engine compression brakes will be minimised.</li> <li>• On-site storage capacity will be maximised to reduce the need for truck movements during sensitive times.</li> </ul>
Vibration minimum working distances	<p>If vibration intensive equipment is to be used within the minimum working distances for cosmetic damage, as presented in Table 24, then it is recommended that attended vibration measurements are undertaken when work commences, to determine "site specific minimum working distances".</p> <p>The minimum working distances for cosmetic damage from Table 24 are generally considered to be conservative and working within them would not necessarily result in damage however as factors such as work practices and intervening structures can affect vibration levels.</p> <p>In addition, vibration intensive work should not proceed within the site specific minimum working distances unless a permanent vibration monitoring system is installed approximately one metre from the building footprint, to warn operators (e.g. via flashing light, audible alarm, SMS) when vibration levels are approaching the peak particle velocity objective. It is also advisable to carry out building condition surveys of sensitive historical structures before construction work begins.</p>

Action required	Safeguard details
<b>Path controls</b>	
Shield stationary noise sources such as pumps, compressors, fans, etc.	Stationary noise sources will be enclosed or shielded to the greatest extent possible whilst ensuring that the occupational health and safety of workers is maintained.
Shield sensitive receivers from noisy activities	Structures to shield residential receivers from noise will be used such as site shed placement, earth bunds, fencing, and erection of operational stage noise barriers (where practicable).

### 7.1.2 Community consultation and complaints handling

All residents and sensitive receivers impacted by noise levels from the Proposal which are expected to exceed the NML should be consulted prior to the commencement of the particular activity, with the highest consideration given to those that are predicted to be most affected as a result of the works.

The information provided to the receivers would include:

- programmed times and locations of construction work
- the hours of proposed works
- construction noise and vibration impact predictions
- construction noise and vibration mitigation measures being implemented on site.

Community consultation regarding construction noise and vibration would be detailed in a Community Liaison Plan for the construction of the Proposal and would include a 24 hour hotline and complaints management process.

### 7.1.3 TfNSW's CNVS - Additional mitigation measures

TfNSW's CNVS provides practical guidance on how to minimise, to the fullest extent practicable, the impacts on the community from airborne noise, ground-borne noise and vibration generated during the construction of TfNSW projects. This is managed through the application of all feasible and reasonable mitigation measures. Where exceedances are still expected to occur after standard mitigation measures have been applied, the CNVS recommends the implementation of additional mitigation measures. These mitigation measures are specified within the CNVS and presented in Table 28.

The provision of additional mitigation is based on the predicted exceedances above RBLs and when the exceedances occur. The RBLs can be found in Table 6.

**Table 28 How to implement additional airborne noise management levels**

Construction hours	Receiver perception	dB(A) above RBL	dB(A) above NML	Additional management measures
<b>Standard hours</b> Monday-Friday (7am-6pm)  Saturday (8am-1pm)	Noticeable	5 to 10	0	-
	Clearly audible	> 10 to 20	< 10	-
	Moderately intrusive	> 20 to 30	> 10 to 20	PN, V
	Highly intrusive	> 30	> 20	PN, V
	75 dB(A) or greater	N/A	N/A	PN, V, SN
<b>OOHW Period 1</b> Monday-Friday (6pm-10pm)  Saturday (7am-8am, 1pm-10pm)  Sunday/PH (8am-6pm)	Noticeable	5 to 10	< 5	-
	Clearly audible	> 10 to 20	5 to 15	PN
	Moderately intrusive	> 20 to 30	> 15 to 25	PN, V, SN, RO
	Highly intrusive	> 30	> 25	PN, V, SN, RO, RP#, DR#
<b>OOHW Period 2</b> Monday-Saturday (12am-7am, 10pm-12am)  Sunday/PH (12am-8am, 6pm-12am)	Noticeable	5 to 10	< 5	PN
	Clearly audible	> 10 to 20	5 to 15	PN, V
	Moderately intrusive	> 20 to 30	> 15 to 25	PN, V, SN, RP, DR
	Highly intrusive	> 30	> 25	PN, V, SN, AA, RP, DR

Notes: PN = Project notification  
V = Verification monitoring  
RP = Respite period  
AA = Alternative accommodation  
SN = Specific notification, individual briefings, or phone call  
DR = Duration respite  
RO = Project specific respite order

\* SWLs used for the purpose of estimating noise impact shall be increased by 5 dB(A) where works will include: power saws for the cutting of timber, masonry & steel; grinding of metal, concrete or masonry; rock/line drilling; bitumen milling & profiling; jack hammering, rock hammering & rock breaking; or impact piling as a correction factor for noise with special audible characteristics.

# Respite periods and duration reduction are not applicable when works are carried out during OOHW Period 1 Day only (i.e. Saturday 6am-7am & 1pm-6pm, Sundays / Public Holidays 8am-6am)

Table 29 outlines the additional mitigation measures, as outlined in the CNVS.

Table 29 Description of additional mitigation measures

Measure	Description	Abbreviation
Periodic Notification	<p>For each project, a notification entitled 'Project Update' or 'Construction Update' is produced and distributed to stakeholders via letterbox drop and distributed to the project postal and/or email mailing lists. The same information will be published on the TfNSW website (<a href="http://www.transport.nsw.gov.au">www.transport.nsw.gov.au</a>).</p> <p>Periodic notifications provide an overview of current and upcoming works across the project and other topics of interest. The objective is to engage, inform and provide project-specific messages. Advanced warning of potential disruptions (e.g. traffic changes or noisy works) can assist in reducing the impact on stakeholders. The approval conditions for projects specify requirements for notification to sensitive receivers where works may impact on them.</p> <p>Content and length is determined on a project-by-project basis and must be approved by TfNSW prior to distribution.</p> <p>Most projects distribute notifications on a monthly basis. Each notification is graphically designed within a branded template.</p> <p>In certain circumstances media advertising may also be used to supplement Periodic Notifications, where considered effective.</p> <p>Periodic Notification may be advised by the Community Engagement Team in cases where AMMM are not triggered as shown in Tables 9 to 11, for example where community impacts extend beyond noise and vibration (traffic, light spill, parking etc). In these circumstances the Community Engagement Team will determine the community engagement strategy on a case-by-case basis.</p>	PN
Verification Monitoring	<p>Verification monitoring of noise and/or vibration during construction may be conducted at the affected receiver(s) or a nominated representative location (typically the nearest receiver where more than one receiver has been identified). Monitoring can be in the form of either unattended logging (i.e. for vibration provided there is an immediate feedback mechanism such as SMS capabilities) or operator attended surveys (i.e. for specific periods of construction noise).</p> <p>The purpose of monitoring is to confirm that:</p> <ul style="list-style-type: none"> <li>• construction noise and vibration from the project are consistent with the predictions in the noise assessment</li> <li>• mitigation and management of construction noise and vibration is appropriate for receivers affected by the works</li> </ul> <p>Where noise monitoring finds that the actual noise levels exceed those predicted in the noise assessment then immediate refinement of mitigation measures may be required and the Construction Noise and Vibration Impact Statement (CNVIS) amended. Refer to Section 8.4 for more details.</p>	V

Measure	Description	Abbreviation
Specific Notification	<p>Specific notifications are in the form of a personalised letter or phone call to identified stakeholders no later than seven calendar days ahead of construction activities that are likely to exceed the noise objectives. Alternatively (or in addition to), communications representatives from the contractor would visit identified stakeholders at least 48 hours ahead of potentially disturbing construction activities and provide an individual briefing.</p> <ul style="list-style-type: none"> <li>• Letters may be letterbox dropped or hand distributed</li> <li>• Phone calls provide affected stakeholders with personalised contact and tailored advice, with the opportunity to provide comments on the proposed work and their specific needs</li> <li>• Individual briefings are used to inform stakeholders about the impacts of noisy activities and mitigation measures that will be implemented. Individual briefings provide affected stakeholders with personalised contact and tailored advice, with the opportunity to comment on the project</li> </ul> <p>Specific notifications are used to support periodic notifications, or to advertise unscheduled works and must be approved by TfNSW prior to implementation/distribution.</p>	SN
Respite Offer	<p>The purpose of a project specific respite offer is to provide residents subjected to lengthy periods of noise or vibration respite from an ongoing impact. The offer could comprise pre-purchased movie tickets, bowling activities, meal vouchers or similar offer. This measure is determined on a case-by-case basis, and may not be applicable to all projects.</p>	RO
Alternative Accommodation	<p>Alternative accommodation options may be provided for residents living in close proximity to construction works that are likely to incur unreasonably high impacts. Alternative accommodation will be determined on a case-by-case basis and should provide a like-for-like replacement for permanent residents, including provisions for pets, where reasonable and feasible.</p>	AA
Alternative construction methodology	<p>Where the vibration assessment identifies that the proposed construction method has a high risk of causing structural damage to buildings near the works, the proponent will need to consider alternative construction options that achieve compliance with the Vibration Management Levels (VMLs) for building damage. For example, replace large rock breaker with smaller rock breakers or rock saws.</p>	AC



Measure	Description	Abbreviation
Respite Period	OOHW during evening and night periods will be restricted so that receivers are impacted for no more than 3 consecutive evenings and no more than 2 consecutive nights in the same NCA in any one week. A minimum respite period of 4 evenings/5 nights shall be implemented between periods of consecutive evening and/or night works. Strong justification must be provided where it is not reasonable and feasible to implement these period restrictions (e.g. to minimise impacts to rail operations), and approval must be given by TfNSW through the OOHW Approval Protocol (Section 6). Note; this management measure does not apply to OOHW Period 1 – Days (See Table 1).	RP
Duration Reduction	<p>Where Respite Periods (see management measure above) are considered to be counterproductive to reducing noise and vibration impacts to the community it may be beneficial to increase the number of consecutive evenings and/or nights through Duration Reduction to minimise the duration of the activity. This measure is determined on a project-by-project basis, and may not be applicable to all projects.</p> <p>Impacted receivers must be consulted and evidence of community support for the Duration Reduction must be provided as justification for the Duration Reduction. A community engagement strategy must be agreed with and implemented in consultation with Community Engagement Representatives.</p>	DR

## 8.0 Conclusion

A Noise and Vibration Impact Assessment has been completed for the construction of a new substation at 166 O’Riordan Street, Mascot (the Proposal). Nearby noise and vibration sensitive receivers were identified. Attended and unattended noise measurements were undertaken to characterise the existing noise environment. The measured noise levels were used to establish operational noise criteria and construction NMLs.

### 8.1 Construction noise

Construction work packages have been developed in consultation with TfNSW and the proposed equipment has been detailed within this report. Two distinct representative construction stages were used in a computer-based noise model to determine the predicted noise levels generated from the Proposal.

The predicted construction noise levels exceed the construction NMLs at some receivers. The magnitude and number of exceedances are detailed in Section 4.4.

Measures have been recommended to mitigate construction noise impacts upon nearby sensitive receivers.

The final number, degree and nature of these measures would be selected by the contractor and be largely dependent on the construction strategy and work carried out. Specific noise management and mitigation measures would be detailed in the contractor’s CNVMP. The recommended management and mitigation measures which would be considered in the plan include:

- effective communication with community and affected receivers about mitigation measures
- training of construction site workers
- use of temporary noise barriers
- monitoring
- appropriate selection and maintenance of equipment
- scheduling of work for less sensitive time periods
- situating plant in less noise sensitive locations
- construction traffic management
- respite periods.

#### 8.1.1 Construction traffic

An assessment of the likely construction traffic indicated that increases in road traffic noise levels would be lower than the 2 dB(A) threshold outlined in the RNP. Therefore, no further assessment of construction traffic is required in accordance with the RNP.

### 8.2 Construction vibration

Minimum working distances to nearby structures have been recommended for nominated plant. If the minimum working distances are maintained, then no adverse impact from the vibration intensive works are likely in terms of human response or cosmetic damage. It is unlikely that work would be undertaken within the minimum working distances for heritage, commercial and residential receivers during the proposed vibration intensive works. Should works be required within the minimum working distances, the recommended additional mitigation measures would be implemented.

### 8.3 Operational noise

An operational noise assessment was undertaken in accordance with the NPfl. The results of this assessment found that the predicted noise levels associated with the operation of the new substation at Mascot were below the noise trigger levels determined in accordance with the NPfl. It is

recommended that the noise emissions be reviewed once the final equipment selections have been made. Based on the equipment noise level assumptions, no further mitigation is proposed.

# Appendix A

## Acoustic terminology

## Appendix A Acoustic terminology

The following is a brief description of acoustic terminology used in this report.

<i>Sound power level</i>	The total sound emitted by a source.																						
<i>Sound pressure level</i>	The amount of sound at a specified point.																						
<i>Decibel, dB</i>	The measurement unit of sound.																						
<i>A Weighted decibels, dB(A)</i>	The A weighting is a frequency filter applied to measured noise levels to represent how humans hear sounds. The A-weighting filter emphasises frequencies in the speech range (between 1kHz and 4 kHz) which the human ear is most sensitive to, and places less emphasis on low frequencies at which the human ear is not so sensitive. When an overall sound level is A-weighted it is expressed in units of dB(A).																						
<i>Decibel scale</i>	The decibel scale is logarithmic in order to produce a better representation of the response of the human ear. A 3 dB increase in the sound pressure level corresponds to a doubling in the sound energy. A 10 dB increase in the sound pressure level corresponds to a perceived doubling in volume. Examples of decibel levels of common sounds are as follows: <table> <tr> <td>0dB(A)</td> <td>Threshold of human hearing</td> </tr> <tr> <td>30dB(A)</td> <td>A quiet country park</td> </tr> <tr> <td>40dB(A)</td> <td>Whisper in a library</td> </tr> <tr> <td>50dB(A)</td> <td>Open office space</td> </tr> <tr> <td>70dB(A)</td> <td>Inside a car on a freeway</td> </tr> <tr> <td>80dB(A)</td> <td>Outboard motor</td> </tr> <tr> <td>90dB(A)</td> <td>Heavy truck pass-by</td> </tr> <tr> <td>100dB(A)</td> <td>Jackhammer/Subway train</td> </tr> <tr> <td>110 dB(A)</td> <td>Rock Concert</td> </tr> <tr> <td>115dB(A)</td> <td>Limit of sound permitted in industry</td> </tr> <tr> <td>120dB(A)</td> <td>747 take off at 250 metres</td> </tr> </table>	0dB(A)	Threshold of human hearing	30dB(A)	A quiet country park	40dB(A)	Whisper in a library	50dB(A)	Open office space	70dB(A)	Inside a car on a freeway	80dB(A)	Outboard motor	90dB(A)	Heavy truck pass-by	100dB(A)	Jackhammer/Subway train	110 dB(A)	Rock Concert	115dB(A)	Limit of sound permitted in industry	120dB(A)	747 take off at 250 metres
0dB(A)	Threshold of human hearing																						
30dB(A)	A quiet country park																						
40dB(A)	Whisper in a library																						
50dB(A)	Open office space																						
70dB(A)	Inside a car on a freeway																						
80dB(A)	Outboard motor																						
90dB(A)	Heavy truck pass-by																						
100dB(A)	Jackhammer/Subway train																						
110 dB(A)	Rock Concert																						
115dB(A)	Limit of sound permitted in industry																						
120dB(A)	747 take off at 250 metres																						
<i>Frequency, Hz</i>	The repetition rate of the cycle measured in Hertz (Hz). The frequency corresponds to the pitch of the sound. A high frequency corresponds to a high pitched sound and a low frequency to a low pitched sound.																						
<i>Equivalent continuous sound level, <math>L_{eq}</math></i>	The constant sound level which, when occurring over the same period of time, would result in the receiver experiencing the same amount of sound energy.																						
$L_{max}$	The maximum sound pressure level measured over the measurement period.																						
$L_{min}$	The minimum sound pressure level measured over the measurement period.																						
$L_{10}$	The sound pressure level exceeded for 10% of the measurement period. For 10% of the measurement period it was louder than the $L_{10}$ .																						

<i>L<sub>90</sub></i>	The sound pressure level exceeded for 90% of the measurement period. For 90% of the measurement period it was louder than the L <sub>90</sub> .
<i>Ambient noise</i>	The all-encompassing noise at a point composed of sound from all sources near and far.
<i>Background noise</i>	The underlying level of noise present in the ambient noise when extraneous noise (such as transient traffic and dogs barking) is removed. The L <sub>90</sub> sound pressure level is used to quantify background noise.
<i>Traffic noise</i>	The total noise resulting from road traffic. The L <sub>eq</sub> sound pressure level is used to quantify traffic noise.
<i>Day</i>	The period from 0700 to 1800 h Monday to Saturday and 0800 to 1800 h Sundays and Public Holidays.
<i>Evening</i>	The period from 1800 to 2200 h Monday to Sunday and Public Holidays.
<i>Night</i>	The period from 2200 to 0700 h Monday to Saturday and 2200 to 0800 h Sundays and Public Holidays.
<i>Assessment background level, ABL</i>	The overall background level for each day, evening and night period for <b>each day</b> of the noise monitoring.
<i>Rating background level, RBL</i>	The overall background level for each day, evening and night period for the <b>entire length</b> of noise monitoring.
<i>Weighted sound reduction index [R<sub>w</sub>]</i>	A single figure representation of the air-borne sound insulation of a partition based upon the R values for each frequency measured in a laboratory environment.

\*Definitions of a number of terms have been adapted from Australian Standard AS1633:1985 “Acoustics – Glossary of terms and related symbols”, the EPA’s NSW Noise Policy for Industry and Road Noise Policy.

# Appendix B

Logging results

# Noise Logger Report

282 King Street, Mascot



Item	Information
Logger Type	NL-52
Serial number	876010
Address	282 King Street, Mascot
Location	282 King Street, Mascot
Facade / Free Field	Free Field
Environment	Noise environment dominated by road traffic noise on King Street and aircraft takeoff noise from airport. People talking on other side of the road clearly audible. Some truck movements from nearby industry just audible. Helicopter flyover 63 dB(A)

## Measured noise levels


Logging Date	L <sub>Aeq</sub> Day	Eve	Night	ABL Day	Eve	Night	L <sub>Aeq</sub> 15hr	L <sub>Aeq</sub> 9hr
Fri Oct 18 2019	66	66	58	-	44	-	66	58
Sat Oct 19 2019	64	60	54	-	-	40	63	54
Sun Oct 20 2019	59	58	53	42	41	36	59	53
Mon Oct 21 2019	66	65	58	46	40	37	66	58
Tue Oct 22 2019	67	65	60	46	40	37	66	60
Wed Oct 23 2019	66	64	60	47	43	36	66	60
Thu Oct 24 2019	63	65	58	45	45	37	64	58
Fri Oct 25 2019	65	-	58	-	-	-	65	58
<b>Summary</b>	<b>65</b>	<b>64</b>	<b>58</b>	<b>46</b>	<b>42</b>	<b>37</b>	<b>65</b>	<b>58</b>

Note: Results denoted with '-' do not contain enough valid data for a value to be calculated. The data has been excluded either manually or automatically as a result of adverse weather conditions.


Logger Location	Logger Deployment Photo




## Typical Day




## Friday, 18 Oct 2019




## Saturday, 19 Oct 2019




Sunday, 20 Oct 2019




Monday, 21 Oct 2019




Tuesday, 22 Oct 2019




Wednesday, 23 Oct 2019



Thursday, 24 Oct 2019




Friday, 25 Oct 2019



# Appendix C


## Construction noise contours




- |  |                          |
|--|--------------------------|
| <b>Sound Pressure Level, <math>L_{Aeq}</math>, dB(A)</b> | <b>Active Recreation</b> |
| Highly Noise Affected Level $\geq 75$ dB(A)              | Commercial               |
| Standard Hours NML $\geq 51$ dB(A)                       | Hotel                    |
| Evening NML $\geq 47$ dB(A)                              | Industrial               |
| Night-time NML $\geq 42$ dB(A)                           | Residential              |
|  | School                   |

Mascot Power Supply Upgrade  
**Construction Noise Contours - Site Establishment**

NOV 2019  
 60600277






**Sound Pressure Level,  $L_{Aeq}$ , dB(A)**

- Highly Noise Affected Level  $\geq 75$  dB(A)
- Standard Hours NML  $\geq 51$  dB(A)
- Evening NML  $\geq 47$  dB(A)
- Night-time NML  $\geq 42$  dB(A)

- Active Recreation
- Commercial
- Hotel
- Industrial
- Residential
- School


Mascot Power Supply Upgrade  
**Construction Noise Contours - New Mascot Substation**



NOV 2019  
60600277

# Appendix D

Operational noise  
contours



- Active Recreation
- Commercial
- Hotel
- Industrial
- Residential
- School
- Operational Assessment Receiver
- Proposed Substation Building

